

Excavation & Compaction	MECHANICAL
Lean	2" Thick
Termite Proofing (after 1st Compaction)	Local
Reinforcement (All sizes)	Faizan/Deewan G-60
Foamwork	Partal/Keil Wood
Concrete	Manual Machine Mix at site
Cement (Both SRC & OPC)	Pak Land/Thatta
Backfilling	Excavated soil
Bitumen Coating	Bitumen local
Termite Proofing (after 2nd Compaction)	Local
Block Masoary	Block of 600 PSI
Plaster Internal-Thickness as per drawings	With local Reti
Plaster External-Thickness as per drawings	With local Reti
Electrical Conduit	Civic/Nawab/
Sewerage Pipr for conduiting	Pak Arab/Civic/Prince