Excavation & Compaction	MECHANICAL
Lean	3" Thick
Termite Proofing (after 1st Compaction)	Imported
Reinforcement (All sizes)	Amreli/Agha G-60
Foamwork	Partal/Keil wood
Concrete	Manual Machine Mix at site
Cement (Both SRC & OPC)	Lucky/Power
Backfilling	Excavated soil
Bitumen Coating	Bitumen local
Termite Proofing (after 2nd Compaction)	Imported
Block Masoary	Block of 800 PSI (crush made)
Plaster Internal-Thickness as per drawings	With Nooriabad Farsh Naddi Reti
Plaster External-Thickness as per drawings	With Nooriabad Farsh Naddi Reti
Electrical Conduit	Jaddah/Galco
Sewerage Pipr for conduiting	Steelex/Dadex